

ROYAL ALBERT HALL – VERDI RESTAURANT FAN COIL UNIT INSTALLATION

Client	Royal Albert Hall
Consultant	N/A
Contract	Installation of 3No New Fan Coil Units
Contract Value	£45,000
Contract Duration	6 weeks
Works Description	<p>This project was based in London at The Royal Albert Hall.</p> <p>All works were carried out “Out of Hours”.</p> <p>The project consisted of the following:</p> <ul style="list-style-type: none"> • Supply and installation of 3 No. Fan Coil Units (FCU’s) above the decorative raft. • Connection into the existing LTHW and CHW pipework within adjacent plant room. • All associated builders work in connection, including forming opening in the ceiling void and making good. • Extension of LTHW and CHW pipework to serve the new FCU’s. • Installation of continuous diffuser within the entrance raft ceiling. • Supply and installation of new Plenum boxes onto the diffusers. • Installation of new insulated flexible ductwork from the FCU’s to new Plenum Boxes. • Thermal insulation to all new pipework and ductwork. • Installation of new Automatic controls, connected back into the existing system and commissioned. • Extension of small power circuit from local distribution board to serve the new FCU’s. • All associated testing and commissioning work.

