

THE ETONS	
Client	Parkgate Aspen Ltd
Consultant	Tuffin Ferraby Taylor LLP
Contract	Replacement of 6No CWS Storage Tanks across 3No 1930's residential blocks
Contract Value	£187,443.07
Contract Duration	7 Months
Completion	October 2018
Works Description	<p>Replacement of 6no CWS storage tanks across 3no 1930's residential blocks.</p> <p>Eton Rise, Eton Hall and Eton Place, each housing over 100 flats.</p> <p>The contract comprised of temporary MCWS supplies to existing GWDS in a phased manor whilst removal of existing and installation of new were being carried out.</p> <p>Due to the age and condition of the existing galvanised system, close liaison was required with residents and site porters to ensure water services were kept live during operations and equipment changeovers.</p> <p>A later instruction included cutting in branch isolation valves to each distribution service on each roof.</p> <p>This work included asbestos cleaning of pipework and again close liaison with residents when shutting services down.</p> <p>Other services included in this project.</p> <ul style="list-style-type: none"> • Thermal insulation • Asbestos removals • Tank Room Lighting • Tank Supports • Decoration of tank room floors

